

2008 – I-85 / Kia Boulevard Bridge

Description

Meta Fields

Specifications 0 Spec File: 2314

Abc Construction Equipment: Conventional

Miscellaneous Prefabricated: bars in splice coupler, grouted duct connection (in precast

substructure)

Prefabricated Bridge Elements: precast cap & column(s)

Contracting: incentive / disincentive clause

Project Delivery: design-build

Longitude: -85.108383 **Latitude:** 32.929783

Nbi #: 285-00309X-001.11E

State Id #: 285-5071-0

Construction Equipment: Conventional

Total Bridge Length Ft: 384
Max Span Length Ft: 132
Beam Material: Concrete
Spans: > Three-span
Location: Rural

Owner: State
State: GA

Year Abc Built: 2008 Contract Plans: 2

Additional Information: <u>I-85 Interchange Design-Build Project Using Prefabricated Bridge Elements in West Point, GA, Final Report, June 2013, Highways for LIFE, Federal Highway Administration, U.S. Department of Transportation</u>

Department of Transportation

Incentive Program: HfL (Highways for Life): \$1,000,000

Funding Source: Federal and State

Costs: The engineerâ€[™]s estimate for this project was \$4.03 million. The low bid was \$3.36 million (\$670,000 = 16% lower than engineerâ€[™]s estimate). There were four bidders. The cost per square foot of bridge was \$74 compared to \$88 for conventional construction in this region in 2008.

Estimated construction cost savings were \$670,000 relative to conventional construction. In addition, the project was constructed in only 16.5 months, resulting in estimated delay-related user cost savings

of \$550,000 and safety cost savings of \$750,000 for a total estimated savings of \$2 million.

Contacts: Owner: Bill DuVall, P.E. State Bridge Engineer Georgia Department of Transportation bduvall@dot.ga.gov 404-631-1883

Stakeholder Feedback: The project showed that the use of precast elements was a viable technique for bridge construction. In particular, the grouted rebar splices worked very well. The Department will use this technique on other bridges as the need arises.

Construction Method: The precast caps and columns were fabricated offsite in a controlled environment, shipped to the site using conventional semitrailers, and temporarily stored onsite after delivery. The contractor closed one lane of I-85 and offloaded up to four columns and pier caps at a time. Lane closure was kept to a minimum, normally for 1.5 hours or less, and occurred during nonpeak traffic hours. Cast-in-place column footings were constructed ahead of time with protruding reinforcing steel that fit into a specialized coupler on the bottom of the columns. A bed of high-earlystrength grout was placed on the footing to receive the column, the column was erected, and additional specialized grout supplied by the manufacturer was hand pumped into the coupler's inlet holes. The columns were then checked for alignment with surveying equipment. Two columns per day were set early in the project, increasing to four columns per day as experience grew. The pier caps were placed on top of the columns similar to the way the columns were set on the foundations except that the specialized couplers in the pier cap were required to simultaneously line up with reinforcing bars from the two adjacent columns. A steel jig was placed on top of the neighboring column as they were set to ensure proper alignment. Once the alignment was checked with the jig, the contractor was able to set one interior substructure (four pier caps) in one day. The Request for Proposal special provisions for this design-build project included an innovative contracting approach requiring the contractor to propose state-of-the-art methods to achieve specified performance goals, therein providing innovative recommended methods for monitoring and reporting various performance measures to achieve the Highways for LIFE goals. The Georgia DOT required the contractor to define the performance measure methods as project deliverables tied to an incentive-disincentive approach, which is unique in Georgia. Execution is as enforceable as any other deliverable in the contract. Data reporting assessment will help determine the performance measures for future Georgia DOT construction contracts.

Replacement Or New Bridge: Each of the three interior substructures of this new bridge consists of eight 3.5-ft-square precast columns with four 4-ft-square precast pier caps joining two columns each. Abutments were conventional cast-in-place backwalls and wingwalls on steel H piles. The conventional superstructure cross-section consists of fourteen 72-inch-deep pretensioned bulb tee girders at 8.5-ft spacing in the 132-ft spans, and twelve AASHTO Type II pretensioned I-shaped beams at 8.5-ft spacing and 72-inch-deep bulb tee girder fascia beams in the 60-ft-long spans. Decks were cast-in-place after beam erection.

Existing Bridge Description: N/A

Traffic Management: extended use of detour [Average Daily Traffic Count, 2008 - Kia Boulevard:

8,600; Interstate 85: 31,000]

Average Daily Traffic At Time Of Construction: 31000

Dimensions: 384-ft-long and 119.25-ft-wide four-span prestressed concrete bulb tee girder bridge (60 ft â€" 132 ft â€" 60 ft)

Primary Drivers:

- reduced traffic impacts
- reduced onsite construction time
- improved work-zone safety

Impact Category: Tier 6 (longer but reduced by months/years) **Mobility Impact Time**:

ABC: 16.5 months of I-85 shoulder closure
Conventional: 30 months of traffic impact

Project Location : CR 98 (Kia Boulevard) over I-85 near the city of West Point in west central Georgia **Project Summary :** The three interior piers on this new bridge consist of precast concrete caps and columns.